

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-02/2020-21 Dt:06-5-2020

APPROVED TENDER SCHEDULE -'B'


Item-13


Name of Work :-Additional grant for construction of parking lots at 16th A & B cross roads in ward no:04 of Yelahanka Satellite town sub division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri K B ALANKAR	
				Rate	Rate in Words
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. complete as per specifications and directions of Engineer in charge.	cum	348.02	350.26	Three Thousand Nine Hundred FiftyThree Paise ThirtyNine Only
2	Construction of Embankment with Material Gravel/ Murrum. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density) complete as per specifications and directions of Engineer in charge.	cum	348.02	361.55	Three Hundred SixtyFour Paise Seven Only
3	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications and directions of Engineer in charge.	cum	207.15	5778.17	Four Hundred SixtyThree Paise SeventyFive Only

	ng and laying in position plain cement ate of mix M20 with OPC cement @ gs, with 20mm and down size graded lite metal coarse aggregates @0.69cum d fine aggretes @ 0.43cum, with uperplastisiser @3lts confirming to IS9103- 1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications and directions of Engineer in charge.	cum	193.90	5927.24	Four Hundred SeventyEight Paise FourtyFour Only
5	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications and directions of Engineer in charge.	cum	176.76	405.88	Five Hundred SixtyTwo Paise ThirtySeven Only
6	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications and directions of Engineer in charge.	cum	83.52	5112.91	Six Hundred SixtyFive Paise Nineteen Only
7	Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:4 , edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications and directions of Engineer in charge.	cum	56.06	6680.38	Seven Hundred ThirtyFour Paise FourtyFour Only

ating, providing and erecting in position dip galvanized Gate. Using 72x72x4.8 Sq. G I Pipe Frame with top pipe ding in heavy duty hydraulic press with and packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanized sq.rod for verticals at 150mm c/c, as shown in the drawing including providing hot do galvanized forged ornamental design in between rods and heads at top, middle and bottom. Intermediate supports of 75x12mm and 50x6mm arch bent to hot dip galvanized flats. The work is inclusive of throughing GI, Flat GI Sqm. rods, placing, welding all the joints including grinding, finishing metal patty, painting two coats enamel painting. The rate is inclusive of all materials Like GI Sq. GI Pipe, GI Forged designs etc., heavy duty hinges are made out of 75mm sold sq. block assembled with 20mm du bearing in three places for each flop. Heavy duty locking arrangement of low places including cost of labour, painting, erection charges using hoist pulley cranes, with all lead and lift, loading, transportation, unloading, scaffolding charges and all other complete as per specifications and directions	sqm	24.00	13092.54	Eight Hundred SixtyFive Paise FiftyNine Only
--	-----	-------	----------	--


Signature of the Contractor


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.